



QUOTATION INQUIRY

To,

No. HWW/ OUT/ 1640

DATE: - 16/10/24

Sub: Shifting of 22 KV HT Cable at Sarthana Water Works of Surat Municipal Corporation.

Dear Sir,

Sealed quotations, duly super scribed and returnable to the office of the undersigned are invited from **LICENSED ELECTRICAL CONTRACTORS** for the followings: -


Description	Qty.	Unit	Rate in Rupees	Total Amount in Rupees
1 Excavation & back filling of Cable Trench up to for shifting of 22 KV HT Cables at Sarthana Water Works.	40	mtr.		
2 Removing the existing HT cable from trench & laying of same cable in new trench including disconnecting and re-connecting the HT cable in HT panel.	60	mtr.		
Total in Figures.				

Terms/conditions of quotation

* Work completion period:	15 Days from the date of work order.
* EMD Details:	Quotation must have Earnest Money Deposit of Rs. 1,000/- by Banker's Cheque, Pay order or Demand Draft, payable at Surat in favour of Surat Municipal Corporation. Quotation without Earnest Money Deposit will not be considered.
* All Taxes/ Duties etc.:	The rates should be inclusive of all taxes, GST, duties etc.
* FOR:	Sarthana Water Works
* Validity of quotation:	120 Days from the date of quotation published.
* Payment condition:	Payment shall be made within 30 days, after satisfactory completion of work at site and submission of bill /invoice. The quantity shown above is approximate and may increase or decrease. Payment will be made as per actual work done at site.
* Scope of work :	<ol style="list-style-type: none"> 1. Dismantling of the 3C x 185 mm² XLPE 22 KV HT Cable from the HT Panel and dig it out from the ground and put the same 22 KV HT Cable back into the ground in another cable trench and Re-connect the 22 KV HT Cable to the HT Panel. 2. The depth of trench shall be minimum 1.05 m and width shall be sufficient for laying of 2 no. of 3C x 185 mm² XLPE HT cables. The excavation shall be properly restated as per original. 3. Use of HV self amalgamation tape and other sealing materials as per site requirement and as directed by site in charge shall be in the scope of the contractor without any extra cost. 4. Site Verification should be done at Sarthana Water Works before quoting for the work. 5. Contractor shall arrange personal protective equipment's for his employees as per Site conditions.

	<p>6. Contractor shall assure the safety of the work and personnel and contractor shall be entirely responsible for any damage or injuries to any property or person resulting from any accident due to any reasons.</p> <p>7. The corporation shall not be responsible for any death / accident / injury to the workman / staff of the Contractor or third party, it is contractor's responsibility to take insurance of his employees, medical facility work compensation etc. as per workman compensation act and all other relevant laws. Further the corporation will not provide any insurance / medical facility, workman compensation etc. to the staff of contractor.</p>
*	<p>Rates must be filled in this quotation paper only and returned duly sealed & signed on or before Dt. 29/10/2024 to the office of Executive Engineer, Head Water Works, Surat Municipal Corporation. Fulfilment of this condition is must or else the quotation shall be liable for outright rejection.</p>
*	<p>Quotation envelope containing EMD, duly filled, signed and stamped quotation paper along with price quotation format on company's letter head should be properly sealed and super scribed as "Quotations for Shifting of 22 KV HT Cable at Sarthana Water Works of Surat Municipal Corporation".</p>

Thanking You,


Executive Engineer
Head Water Works
Surat Municipal Corporation

SEAL & SIGNATURE OF CONTRACTOR