

SURAT MUNICIPAL CORPORATION

South West (athwa) Zone


Supply and Erection of Fire System in T.P. 6 (Majura-KHatodara), F.P. No. 4 Majura Fire Station in South West (athwa)

Zone

schedule B

Sr. No.	S.F.A. No.	SR	Description	Qty.	Unit	Supply with Installation & GST Rate	Total Cost
A			FIRE HYDRANT SYSTEM AND PIPING				
1	16		SUPPLY & INSTALLATIONS FIRE PUMP @ 450 LPM 70 Mtr Head - FIRE ELECTRIC MAIN PUMP MAKE:- KIRLOSKAR/LUBI/KSB	1	No	92040	92040
2	21		Fire Pump Control Panel-Auto & Manual Type SUPPLY & INSTALLATION & Testing of Electric Control Panel for Electric Main Fire Pump (Pumps Can be start Automatically by Pressure Switch & Manually as per BOQ. MAKE of Switch Gear:- L.T./C&S	2	No	49560	99120
3			Providing and erecting Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for. 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables MAKE :- RR/Dnyrab				
A	22		4 core 10 Sq. mm	160	Mtr	180	28800
4			Supplying, installing, testing and commissioning of GI Pipes "C" class conforming to IS 1239. 6 mm thick. with specials such as Tees, elbows, flanges. Including cutting, Welding, fixing in / on walls, ceiling by using suitable etc. as per drawing. Make : Jindal/ Asian				
A	17		50 mm dia.	110	Mtr	1120	123200
5			Supplying and Painting the exposed G.I. pipes with one coat of Zinc Chromite primer with two coats of synthetic enamel paint of approved colour / shade. MAKE : Asian/ Berger				
A	38		50 mm dia.	110	Mtr	50	5500
6			Supplying, installing, testing and Commissioning of S.S chrome finished Ball Valves with fittings of screwed end type. Make: Honeywell/Sant/ Zoloto				
A	27		15 mm nominal dia	5	No	860	4300
7			Supply, installation, testing & commissioning of cast iron body Butterfly valve according to IS:13095, PN-1.6, ISI mark, below Lever operated and above 150 mm dia. Gear operated complete with mating flanges/ANSI class# 150 with bolts & nuts washers, rubber gaskets 3mm thick, etc., with all complete. Make:- zoloto/Audco				
A	11		50 mm dia.	4	No	4950	19800
8			Supply, installation, testing & commissioning of cast iron body NRV conf. to IS:5312, PN-1.6, Dual Plate type with S.S flap, IS mark, complete with mating Flanges/IS/ANSI class#150 with bolts & nuts, washers, gaskets 3mm thick, etc., with all complete. Make:- zoloto/Audco				
A	12		50 mm dia.	1	No	5200	5200
9	30		Providing fixing testing and commissioning of Gun metal Two way fire brigade Inlet as per IS:904 having 63mm dia Inlet with blank cap and chain with necessary fittings flanges, nut bolts.etc. Make: NEWAGE/AAAG/Swati	3	No	5600	16800
10	3		Supplying and fixing First Aid hose reel 19mm x 30mtr long with MS construction spray painted in post office red, conforming to IS 884 with upto date amendments, complete with the following as required. Make: NEWAGE/AAAG/Swati	7	No	12500	87500
11	29		Supplying and fixing approved make 25 mm dia with automatic Air Release Valve with unions etc. complete. Make : SANT/ZOLOTO	7	No	2150	15050
12	34		The Following descriptive photoluminescent Green or Red colour safety signages in different sizes / graphics / colours / text can be made according to the standards accepted by the local fire Service Department. Size : 12 X 4 Fire Hydrant - with symbol Fire Hydrant & Hosereel - with symbol Fire Extinguisher - with symbol Arrow downwards + Running man + Emergency exit - with symbol. In case of fire break the glass - with Manual Call Point symbol.	11	No	384	4224
13	9		Providing and fixing of dial type Pressure Guage having 100 mm dial & range of 0-15 Kg/cm2 with syphon and cock. Make : Baumer/H Guru	2	No	1200	2400
14	31		Providing and fixing of CI body Footvalve having 80 mm dia Make : Normax	3	No	9440	28320

15	35	Providing & Fixing of M.S. Structural work fabricated from standard sections, (MS rounds, angles, channels etc) including cutting, drilling, welding, including cost of fasteners etc.	50	Kg.	120	6000
FIRE EXTINGUISHERS						
16		Supplying & erecting ABC powder type Fire extinguisher as per IS 13849 with necessary clamp for erection on wall Make: Kanex/Safex/SecureZone	0	No	3810	0
A	2	6 Kg Capacity				
17		Supplying & erecting carbon dioxide (CO2) fire extinguisher user of following capacity with necessary clamps made from 50 x 6 mm M.S. Flat with nut & bolts grouted in wall complete. Make: Kanex/Safex/SecureZone	0	No	9590	0
A	1	4.5 Kg Capacity				
ALARM SYSTEM						
18	26	Supply and Installation of 2 Zone Alarm Panel Make : System Sensor/ AGNI	1	No	25200	25200
19	23	Supply, installation, testing Of Manual Call Point Make : System Sensor/ AGNI	5	No	3860	19300
20	24	Supply, installation, testing Of Hooter. Make : System Sensor/ AGNI	5	No	1560	7800
21	33	Supply and Installation of Alarm Panel Cable 2 Core 1.5 sq. mm Copper Armoured. Make : RR/ Polycab	170	Mtr	120	20400
Total						610954.00
18.60 % below as per tender condition						113637.44
Total Amount						497316.56


Executive Engineer
South West (athwa) Zone
Surat Municipal Corporation

કાર્યપાલક ઈજનેર
સાઉથ વેસ્ટ (અઠવા) ઝોન,
આદર્શભવનની બાજુમાં, અઠવાલાઈન્સ,
સુરત મહાનગરપાલિકા, સુરત.



ફોન નંબર : ૨૬૬૩૦૪૯-૫૦

૨૬૬૭૯૨૬

મ્યુનિસિપલ ઝોન ઓફિસ, સુરત.

નં.સા.વે.(અઠવા) ઝોન/આ.નં. ૬૦૩૯
તારીખ : ૧૨/૧૨/૧૪

પ્રતિ,
કાર્યપાલક ઈજનેરશ્રી,
સાઉથ-વેસ્ટ (અઠવા) ઝોનલ
આદર્શભવનની બાજુમાં, અઠવાલાઈન્સ,
સુરત મહાનગરપાલિકા, સુરત.

વિષય - સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં ટી.પી. ૦૬ (મજુરા- ખટોદરા), ફા. પ્લોટ નં.૦૪ ખાતે મજુરા ફાયર સ્ટેશનમાં ફાયર સેફ્ટી સીસ્ટમ સપ્લાય કરી ઈસ્ટોલ કરવાનું કામ.

મહાશય,

ઉપરોક્ત વિષયે જણાવવાનું કે, સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં ટી.પી. ૦૬ (મજુરા- ખટોદરા), ફા. પ્લોટ નં.૦૪ ખાતે મજુરા ફાયર સ્ટેશનમાં ફાયર સેફ્ટી સીસ્ટમ સપ્લાય કરી ઈસ્ટોલ કરવાના કામે સેન્ટ્રલ ઝોન વિસ્તારમાં આવેલ વિવિધ મ્યુનિસિપલ સ્કુલ બિલ્ડીંગોમાં ફાયર સેફ્ટી સીસ્ટમ સપ્લાય કરી ઈસ્ટોલ કરવાના તથા પાંચ વર્ષના કોમ્પ્રિહેન્સીવ એન્યુઅલ મેઈન્ટેનન્સ સહિતની કામગીરી કરવાના કામે સ્થા.સ.ઠ.નં. ૧૭૦૬/૨૦૨૨, તા. ૨૦/૧૦/૨૦૨૨ થી મંજુર થયેલ ભાવે અને શરતે રૂ. ૫,૦૦,૦૦૦.૦૦ (અંકે રૂ. પાંચ લાખ) ની ખર્ચ મર્યાદામાં કામગીરી કરવા માટે આપનું સંમતિપત્રક, ઈ.એમ.ડી. રૂ.૫,૦૦૦/- (ડીમાન્ડ ડ્રાફ્ટ/ પે ઓર્ડર) સહિત નીચે જણાવ્યા મુજબનાં ફોર્મેટમાં ભરી અત્રેની કચેરીમાં તા.૨૧.૧૧.૨૦૧૪ના રોજ સાંજે ૬:૦૦ કલાક સુધીમાં નીચે સહી કરનારને મળે એ રીતે મોકલવાના રહેશે. વધુમાં નીચે જણાવ્યા મુજબની વિગતો અચુક સામેલ કરવાની રહેશે. અન્યથા સંમતિપત્રક માન્ય ગણાશે નહીં.

૧. સોલવંશી સર્ટીફિકેટ રજુ કરવાનું રહેશે.
૨. કરેલ કામના વર્ક કમ્પ્લીશન સર્ટીફિકેટ રજુ કરવાના રહેશે.
૩. રજીસ્ટ્રેશન સર્ટીફિકેટ રજુ કરવાનું રહેશે.

કાર્યપાલક ઈજનેર
સાઉથ વેસ્ટ (અઠવા) ઝોન
સુરત મહાનગરપાલિકા

ઈજારદારની સહિ તથા સિક્કો :-

નામ :-

સરનામું :-

તારીખ :-